

ANNUAL MINING REPORT 2024-25

NMDC Limited - Bailadila Iron Ore Project

Report Reference: NMDC/BIOM/2024-25/MR/002

1. MINE DETAILS

Mine Name:	Bailadila Deposit 14/11C
Location:	Dantewada, Chhattisgarh, India
District:	Dantewada
State:	Chhattisgarh
Company:	NMDC Limited
Mineral:	Iron Ore (Haematite)
Mining Method:	Opencast
Report Period:	FY 2024-25 (April 2024 to March 2025)
Date of Report:	22-05-2025

2. PRODUCTION SUMMARY

- Total iron ore extracted during FY 2024-25: 12.8 million tonnes
- Lump ore: 6.1 million tonnes
- Fines: 6.7 million tonnes
- Average Fe content: 64.8 per cent
- Silica: 2.1 per cent, Alumina: 1.9 per cent

3. GEOLOGICAL FINDINGS

The Bailadila range hosts high-grade haematite within the Bailadila Iron Ore Formation of the Bastar craton. The ore body at Deposit 14 is a tabular lode conformable with the banded haematite quartzite host rock, traceable along strike for 4.2 kilometres.

Exploration during the year comprised 4,100 metres of core drilling across eighteen holes. Fe grades in the upper benches remain consistent with the resource model; a localised zone of higher alumina was delineated in the southern bench and will be blended at the crushing plant.

4. RESERVE POSITION

- Proved reserves: 210 million tonnes
- Indicated reserves: 96 million tonnes
- Estimated mine life at current rate of extraction: 24 years

ANNUAL MINING REPORT 2024-25

NMDC Limited - Bailadila Iron Ore Project

Report Reference: NMDC/BIOM/2024-25/MR/002

5. ENVIRONMENTAL COMPLIANCE

- Ambient air quality monitored continuously at four stations; PM10 within NAAQS limits.
- Mine water treated and recycled for dust suppression and washery make-up.
- Plantation of 42 hectares completed during the year under the progressive mine closure plan.
- Quarterly returns filed with the State Pollution Control Board without adverse observation.

6. SAFETY

- Zero fatalities recorded during the reporting period.
- All statutory inspections completed as per DGMS circulars.
- Reportable injury rate of 0.11 per lakh tonnes, against a corporate target of 0.20.

7. RECOMMENDATIONS

- Continue exploratory drilling in the eastern block to firm up inferred reserves.
- Commission the second conveyor to reduce road haulage and diesel consumption.
- Review the overburden dump slope design ahead of the monsoon.