

ANNUAL MINING REPORT 2024-25

South Eastern Coalfields Limited - Sohagpur Area

Report Reference: SECL/SHD/2024-25/MR/021

1. MINE DETAILS

Mine Name:	Amlai Underground Mine
Location:	Shahdol, Madhya Pradesh, India
District:	Shahdol
State:	Madhya Pradesh
Company:	South Eastern Coalfields Limited (SECL)
Mineral:	Non-Coking Coal
Mining Method:	Underground
Report Period:	FY 2024-25 (April 2024 to March 2025)
Date of Report:	02-05-2025

2. PRODUCTION SUMMARY

- Total coal extracted during FY 2024-25: 6,20,000 MT
- Peak monthly production: 61,000 MT (February 2025)
- Average daily production: 2,100 MT
- Grade band: G8 to G10
- Ash content: 26 to 30 per cent

3. GEOLOGICAL FINDINGS

The Sohagpur coalfield is worked by bord and pillar methods supported by continuous miners in the newer panels. Exploration during the year comprised eleven boreholes totalling 2,640 metres, concentrated along the southern boundary of the lease.

Seam thickness varies between 2.8 and 5.1 metres. The dip is gentle at approximately 1 in 22. Roof conditions are generally good; a localised slip was encountered in panel 7 and was dealt with by additional roof bolting.

4. RESERVE POSITION

- Proved reserves: 74 million tonnes
- Indicated reserves: 29 million tonnes
- Estimated mine life at current rate of extraction: 31 years

ANNUAL MINING REPORT 2024-25

South Eastern Coalfields Limited - Sohagpur Area

Report Reference: SECL/SHD/2024-25/MR/021

5. ENVIRONMENTAL COMPLIANCE

- Ambient air quality monitored continuously at four stations; PM10 within NAAQS limits.
- Mine water treated and recycled for dust suppression and washery make-up.
- Plantation of 42 hectares completed during the year under the progressive mine closure plan.
- Quarterly returns filed with the State Pollution Control Board without adverse observation.

6. SAFETY

- Zero fatalities recorded during the reporting period.
- All statutory inspections completed as per DGMS circulars.
- Reportable injury rate of 0.11 per lakh tonnes, against a corporate target of 0.20.

7. RECOMMENDATIONS

- Continue exploratory drilling in the eastern block to firm up inferred reserves.
- Commission the second conveyor to reduce road haulage and diesel consumption.
- Review the overburden dump slope design ahead of the monsoon.